BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work: Estimate for Desilting of Storm Water Drain in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
1	**11293.75**	KSRRB 200-8 : Cleaning and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and tress of girth upto 300mm by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials within a lead of 100 meters from road boundary, labour charges complete as per specifications. MORTH chapter 2. **No. 135 / Item No. 18.11 / PWD SR 2015-16**	Sqm	6.48	73183.50	Rupees Six and Forty Eight Paise Only
2	**5625.25**	Excavation and removal of silt or silt mixed with sand in slushy condition from canal bed including jack well disposing off the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50 m and all lifts.MISR 2014-15 (P. 76 / I. No. 44)	cum	245.50	1380998.88	Rupees Two Hundred Forty Five and Fifty Paise Only
3	**27.00**	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 **Page No. 23 / Item No. 5.6 / PWD SR 2015-16**	cum	4135.32	111653.64	Rupees Four Thousand One Hundred Thirty Five and Thirty Two Paise Only
4	**45.00**	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4. **Page No. 109 / Item No. 15.3 / PWD SR 2015-16**	Sqm	99.36	4471.20	Rupees Ninety Nine and Thirty Six Paise Only
5	**33.80**	KSRB 4-1.6 : Providing and laying in position plain cement concrete of **mix 1:2:4 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. **No. 12/ Item No. 4.6 / PWD SR 2015-16**	cum	5490.72	185586.34	Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only
6	**5259.61**	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	103.37	543685.89	Rupees One Hundred Three and Thirty Seven Paise Only
		Total			**2299579.44**	

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/11/16